

GOVERNMENT OF PUDUCHERRY
ELECTRICITY DEPARTMENT
KARAIKAL

L.C.E. No. 02 / EDK/EE-V/AEE-C&B /F- 21 /2016- 2017/14, Dt. 24.05.2016

QUOTATION NOTICE

Sub: EDK – Estimate for Re-Routing the existing 11 KV Poovam Feeder (part) by 3X400 sqmm HT UG XLPE Cable, at PT Vasal end, Electricity Department, Karaikal.–Quotation Called for-Reg.

&&&&&

Sealed Quotations are here by invited by the Assistant Executive Engineer / C&B, Electricity Department, Karaikal on behalf of the President of India, from the contractors experienced in the same field of works for the works given below. The Quotations should reach the office on or before 10.00 A.M of 07.06.2016 and the same will be opened at 11.00 A.M on the next day in the office of Assistant Executive Engineer / C&B. Those tenderers who are willing may be present at that time. If the opening date happens to be holly day, the next working day will be treated as the opening day.

NAME OF THE WORK: Re-Routing the existing 11 KV Poovam Feeder (part) by 3X400 sqmm. HT UG XLPE Cable, at PT Vasal end, Electricity Department, Karaikal.

SL.NO.	DESCRIPTION OF ITEM	APP. QTY	UNIT RATE	AMOUNT
1.	Laying of one run of 11KV, 3 x 400 mm XLPE HT UG cable direct in ground including excavation of trench of size 0.5m (W) x 102m (D), river sand cushioning, protective covering with RCC trough and refilling the trench, disposal of unserviceable material as directed etc. (HT Cable will be supplied by the Department)	220	mtrs.	
2.	Supply and providing of RCC trough as specified in the drawing enclosed.	330	nos.	
3.	Providing 18 mt. of GI pipe of size 150mm dia for 11KV cable raising in the existing 4 pole structure with suitable MS clamp.	2	nos.	
4.	Supply & Provision of outdoor end termination kits suitable for 11KV, 400 Sq. mm XLPE HT UG Cable with associated materials.	2	nos.	

Cw
30/5/16

- | | | |
|-----|--|-----------|
| 5. | Supply and concreting of route marker plated at the locations as directed by the Engineer-in-charge (i.e. marker @ 50mt. and to located cable joint) including. | 10 nos. |
| 6. | Labor charge for Erection of 30' RCC pole including excavation of pit and refilling (without concreting). | 1 no. |
| 7. | Labor charge for Concreting of 30' RCC pole in cement concrete foundation 0.45x 0.45x1.5 Mts. and coping 0.45x 0.45x0.45 Mts. with ratio 1:3:6 using 20 mm HBG metal including cost of concreting materials such as cement, jelly, sand etc, excavation and refilling etc., | 1 no. |
| 8. | Labor for the earthing of HT pole by No.8 GI wire. | 2 Nos. |
| 9. | Labor charge for Fixing of HT tapping channel 75x 45x10 mm for 11 KV overhead line including drilling of holes for insulator. | 2 nos. |
| 10. | Labor charge for erection of 11 KV disc insulators for 11 KV overhead lines complete with 11 KV metal parts as required. | 12 nos. |
| 11. | Labor charge for Erection of HT stay Set without concrete. | 2 nos. |
| 12. | Labor charge for Erection of F clamp in poles for 11KV overhead line. | 2 nos. |
| 13. | Labor charge for Erection of 11 KV Pin insulators with G.I pin. | 6 nos. |
| 14. | Labour charges for Straining of ACSR 7/4.09 Conductor | 120 mtrs. |


 24/5
 ASSISTANT EXECUTIVE ENGINEER / C&B

To,

1. M/s. Sun Electrical works, Church street, Karaikal.
2. M/s. Golden Engineering and Consultancy, No.82, Bharathiyar Road, Karaikal
3. Thiru.R.Sakthivel Electricals, Bharathiyar Road, Thalatheru, Karaikal.
4. M/S Kartik Enterprises, No.04, Laporte street, Municipal complex, Puducherry.
5. M/S Jeeva Electricals, No.01, Church street, Karaikal.
6. The Notice Board, Main Office, Electricity Department, Karaikal..
7. The Notice Board, Main Office, PWD, Karaikal
8. The NIC Website, Karaikal.-with a request to display this notice in the NIC website.
9. The Official Website, Electricity Dept. Puducherry. www.electricity.Puducherry.gov.in

Copy Submitted to: The Executive Engineer-V, Electricity Department, Karaikal.

Copy To: 1. The Junior Engineer/Cable, Ed, Karaikal.

2. The Office superintendent, Ed, Karaikal.